

Sustainable CSA Cement-based Precast Concrete Tunnel Lining Reinforced with GFRP Bars: Challenges and Opportunities

THE WORLD'S GATHERING PLACE FOR ADVANCING CONCRETE



Simone SPAGNUOLO

Alberto Meda


Zila Rinaldi



WHY AIM FOR THE CSA BINDERS IN TUNNELLING FIELD?

An average of over
5,000
kilometers
of tunnels are constructed each year
around the world.¹

Approximately
86 billion
Euros are spent per year in tunnel and
underground construction worldwide.¹



60 million m³/year

150 million tons_{Concrete}/year

24 million tons_{Cement}/year


24 millions tons CO₂/year
≈ 1% worldwide




¹ Source: International Tunnelling Association (ITA), Tunnel Market Survey 2016

Increasing use of mechanized tunnelling

Tunnel boring machines are very advanced equipment used as an alternative to drilling and blasting through rock and conventional mechanical excavation in soft ground. Mechanized tunneling has become more important with the rapid growth and expansion of underground construction in recent years.



Production of the precast segments



Work-site storage area: can be a problem?

Stacking on the construction-site

Rural areas



Urban areas

Main advantages...

- More sustainable production process (lower firing temperature)
- **Development of high mechanical strengths in short-term**
- Low shrinkage

...connected to mechanized excavation

$f_c = 12 \div 15 \text{ MPa}$



Fast static-curing
4÷5 hours

No
Steam-curing

Speed up demoulding

Installation: 7 days for the required strength (instead of 28 days)

Increase in production per workshift and fast clearing of the storage areas

Main disadvantages... ...solved in mechanized excavation

- Low workability




Sufficient for the prefabrication

- Low pH value



Traditional Steel reinforcement



New GFRP closed-ring reinforcement




Full-scale test with several GFRP dimensions/configurations


Hydro tunnel



Metro tunnel



Rail tunnel




Road tunnel



Full-scale test on several tunnel dimensions: Bending test



Hydro tunnel



Metro tunnel




Rail tunnel



Road tunnel

Full-scale test on several tunnel dimensions: TBM thrust test



Hydro tunnel



Metro tunnel




Rail tunnel



Road tunnel

Full-scale test on metro tunnel ring: Earth pressure



Experimental program: Concrete Mix design & Reinforcement

Mix design	Unit	20°C	Ref.
Binder (CSA Next-SL05)*	kg/m ³	380	380
Sand	kg/m ³	892	892
Rubble	kg/m ³	445	445
Gravel	kg/m ³	503	503
Additive CC39/P22	%	0.7	0.7
Water	l/m ³	160	160
w/c	-	0.42	0.45
Workability loss (Consistency class: S4)			
t ₀	mm	195	200
t ₃₀	mm	190	200
t ₆₀	mm	180	190

Property	Unit	Value
12 Longitudinal Ø13 (#4) GFRP closed-loop ring		
Average tensile strength	MPa (ksi)	1100 (160)
Guaranteed tensile strength	MPa (ksi)	850 (123)
Design tensile strength	MPa (ksi)	397 (57)
Tensile modulus	GPa (ksi)	46 (6672)
Average tensile strain	%	2.39
Guaranteed tensile strain	%	1.85
Design tensile strain	%	0.77
Fiber volume fraction	%	60
Plus 16 Transversal Ø8 (#2) GFRP closed-loop stirrup		

* Replaces CEM IV/A(PV) 42.5N SR pozzolanic cement, normally adopted to cast tunnel segments.





 **Buzzi Unicem**







THE WORLD'S GATHERING PLACE FOR ADVANCING CONCRETE

 **CONCRETE CONVENTION**



Experimental program: three-point bending test

26 hours after segment casting (compare to 28 days of the traditional solution)



Property →		Cross-area Height x width [cm ²]	Reinforcement			Concrete		Exp. Load		Bending moment				
Solution ↓	Curing time		Type	Longitudinal [sup+inf]	Transversal (stirrups)	f_{ym} [MPa]	$f_{fum}^{(a)}$ [MPa]	Type	$f_{cm,cube}$ [MPa]	$F_{1st\ crack}$ [kN]	F_{max} [kN]	$M_{u,exp}$ [kN·m]	$M_{u,ana}$ [kN·m]	ΔM [%]
OPC + Steel	28 days	30x142	Steel	(12+12) Ø12 [#4]	[#2] Ø8/20	510	-	OPC	48	137	373	186	188	-1.0
CSA + GFRP (I)	26 hours		GFRP	12 rings Ø13 [#4]		-	524	CSA	40	140	380	190	187	+1.6
CSA + GFRP (II)	15 days		GFRP	12 rings Ø13 [#4]		-	524	CSA	58	130	395	197	190	+3.9

Note: ^{a)} $f_{rum} = f_{im} / \gamma_{f,\phi} = 1100 / 2.1$



Experimental program: TBM point load test

30 hours after segment casting (compare to 28 days of the traditional solution)




1 st cycle: TBM progress thrust			Admissible residual crack width
Service Load (1580 kN/pad)	Unloading (100 kN/pad)	Maximum crack width	
Solution ↓	[mm]	[mm]	[mm]
OPC + Steel	0.10	0.10	0.15
CSA + GFRP	0.42	0.15	0.50

2 nd cycle: TBM unblocking thrust (Exceptional load)			Admissible residual crack width
Max TBM capacity (2670 kN/pad)	Unloading (0 kN)	Maximum crack width	
Solution ↓	[mm]	[mm]	[mm]
OPC + Steel	0.25	0.10	0.15
CSA + GFRP	0.80	0.15	0.50



Crack pattern

Thrust side




Case study

Summary of required design checks and factors for transient and final stages (ULS) according to ACI544.7R-16.

Load Case	Phase	Dynamic shock factor	Key design parameter f_{ck} (f_{cd}) (MPa)	M_{Ed} (kN·m)	N_{Ed} (kN)	V_{Ed} (kN)	V_{Rd} (kN)
		β					
1	Demoulding	2.0	15 (10)	-16.7	0	47.8	
2	Storage ^{a)}	-	(5 hours)	-13.1	0	106	107
3	Handling	2.0		-7.3	0	21	
4	Soil pressure (ULS)	-	30 (17) (2 days)	55.8	711	67	135


Note: a) Possible temporary storage on construction-site (which follows demoulding) is accounted for.




Load case 1



Load case 2



Load case 3



Note: Transportation phase is neglected for the purpose of using the CSA

THE WORLD'S GATHERING PLACE FOR ADVANCING CONCRETE

- 1) **Speed up the production** (4÷5 hours) without any energy-intensive steam-curing process
→ switch from 2 work-shift/day to 4 work-shift/day
- 2) **Reduction of segments stacked** waiting for the required strengths → **Segments on demand**;
- 3) Possibility to establish a **work-site full prefabrication** (including ad-hoc modify pultrusion process)
improving the health and socio-economic aspects tied to the **reduction of pollution and traffic congestion** of the urban areas. ↴
(**NO transports by trucks** of the reinforcement cages from the manufacturing plant to the prefabrication one and the segments from the latter to the construction-site)





Sustainable CSA Cement-based Precast Concrete Tunnel Lining Reinforced with GFRP Bars: Challenges and Opportunities

THE WORLD'S GATHERING PLACE FOR ADVANCING CONCRETE

THANK YOU



Simone SPAGNUOLO
spagnuolo@ing.uniroma2.it

