

# Cyclic and Strength Performance of Slab-Beam Superstructure System with UHPC Closure Pour

March 28<sup>th</sup>, 2022

David Garber, PhD, PE

Christina Freeman, PE

Francisco Chitty, PhD

THE WORLD'S GATHERING PLACE FOR ADVANCING CONCRETE



# Outline


- Background
  - Slab Beams
  - Florida Slab Beam (FSB)
  - Ultra-High-Performance Concrete (UHPC)
- Research Objectives
- Joint and Section Development
- Joint Testing
- Full-Scale Beam Testing
- Implementation

# Background


- Slab Beams

Slab beams have been used in construction since prestressing began in the US


## Prestressed Rectangular Slab Units (1955)




## Prestressed Keyed Slab Units (1958)



## Prestressed Voided Slab Units – Sonovoids (1959)





## Prestressed Slab Units – PSU (2008)



# Background

- Slab Beams – Performance

There have been some issues observed with previously used slab beams




Bridge over Danforth Creek near West Palm Beach, FL (Spring 2018)

# Background



- Slab Beams

Poor performance of previous systems led to development of alternate systems

## Precast Composite Slab Span System – PCSS (2005)



## Florida Slab Beam – FSB (2015)



These systems require field placement of large reinforcement

# Background

- Ultra-High-Performance Concrete (UHPC)

<i>Property</i>	<i>Range</i>	
Compressive Strength ( $f'_c$ )	20 to 30 ksi	140 to 200 MPa
Tensile Cracking Strength ( $f_t$ )	0.9 to 1.5 ksi	6 to 10 MPa
Modulus of Elasticity ( $E_c$ )	6,000 to 10,000 ksi	40 to 70 GPa



Source: <https://www.fhwa.dot.gov/research/resources/uahpc/>


THE WORLD'S GATHERING PLACE FOR ADVANCING CONCRETE




# Background

- Ultra-High-Performance Concrete (UHPC)

## Typical (a) Compressive and (b) Tensile UHPC Behavior (Haber, 2016)




(a)



(b)

\*Based on current project UHPC mix designs for large-scale specimens



## Measured Compressive and Tensile UHPC Strengths (FDOT)\*

UHPC Mixes	$f'_c$ (ksi)	$f'_r$ (ksi)
Batch 1	22.52	3.14
Batch 2	24.99	3.44
Batch 3	23.19	2.92
Batch 4	24.14	3.23
Batch 5	22.47	3.10

# Background

- Ultra-High-Performance Concrete (UHPC)

## UHPC Overlays (Haber, 2016)



Source: <https://highways.dot.gov/research/structures/ultra-high-performance-concrete/ultra-high-performance-concrete>

## Precast, prestressed girders and waffle slab systems (source: FHWA)






# Research Objectives

- Develop cross-section and joint region detail for short- to medium-span bridges for use with accelerated construction
- Assess strength and fatigue performance of cross-section and joint
- Recommend fabrication procedures, on-site construction practices, and erection tolerances

# Joint Testing Program



- Test Specimens with Naming Convention



**Note:** 2 tests were performed on each specimen




# Joint Testing Program

- Test Setup



# Joint Testing Program


- Experimental Results



## 18-inch-deep specimens



- Current FSB joint failed much lower than expected
- Modified UHPC joints had similar ultimate capacities to current FSB
- Joint 18A1 had the largest ductility among all the joints
- Sandblasted joint finish was not sufficient for achieving desired bond

Best Performance  
**18A1**




# Joint Testing Program

## • Experimental Results




Fatigue loading did not impact the strength of the joint




# Full-Scale Beam Testing


## • Testing Phases

Phase	$n_{beams}$	Type of Loading	Boundary Conditions and Loading	Other Notes
1	2	service, strength	simply supported; varying loading points	
2	2	fatigue, service, strength	simply supported; varying fixity and loading points	moment distribution; SDCL Approach
3	4	fatigue, service, strength	simply supported; varying loading points	differential camber; moment distribution




Beam Cross Section	Joint Area (for 12-in. depth) (in <sup>2</sup> )	Approx. UHPC Cost (per foot of joint)*	Embedment Length (in)	Splice Length (in)
<b>12A2</b> 	60.8 in <sup>2</sup>	\$78.20	6.375 in.	5 in.

\*based on \$5,000 /cy for UHPC




# Full-Scale Beam Testing

- Beam Design



Design based on 2-lane bridge with 6 slab beams and 28.9' span length

12-inch-deep FSB section with 14 - 0.6" diameter strands




Layer	$y_t$	$n_{strands}$	$F_{strand}$
1	3"	4	10 k
2	7"	2	43.9 k
3	9"	12	43.9 k



# Full-Scale Beam Testing

- Beam Design

Shear and confinement reinforcement based off of current FSB standard with slight modifications






# Full-Scale Beam Testing



- Beam Design

Joint reinforcement based on results from small-scale testing and FHWA "Design and Construction of Field-Cast UHPC Connections"

## Joint A2




Joint reinforcement offset in each beam to allow for beam rotation to avoid reinforcement interference



# Full-Scale Beam Testing

- Beam Design

End region was designed based on AASHTO



# Full-Scale Beam Testing

- Beam Construction

Two beams constructed for service and strength testing







UHPC joint cast at FDOT SRC



# Full-Scale Beam Testing

- FEA for Multi-Girder Configurations


Used ATENA to model different beam and load configurations to determine loading configuration



# Full-Scale Beam Testing





- Load Configuration

Loading based on either half or full-axle of HS-20 truck



# Full-Scale Beam Testing – Two Beam Systems



- Static Load Configurations



These static tests were performed on both two-beam systems (Phase I and Phase II)

# Full-Scale Beam Testing – Two Beam Systems

- Static Load Configuration - Continuous




FC 2-7 was used for Phase II





# Full-Scale Beam Testing – Two Beam Systems

## • Fatigue Load Configurations

### FC 2-5 (Reverse Sinusoidal)



### FC 2-6 (Intermediate Support)



FC 2-5 and FC 2-6 were used for Phase II. Over 4.7 million load cycles were applied to the two-beam system in Phase II. An additional cracking load protocol was also used.

THE WORLD'S GATHERING PLACE FOR ADVANCING CONCRETE




# Full-Scale Beam Testing – Two Beam Systems

- Observations

1. Joint performed well during service, fatigue, and strength testing; no joint debonding or distress was observed throughout testing of both two-beam systems; good transfer of stress between beams






Compression block crushing across joint in  
FIU-1/2  
(Same occurred in FIU-4/5)




# Full-Scale Beam Testing – Two Beam Systems

- Observations
  - FIU-4/5 had similar performance to FIU-1/2 during ultimate strength testing → 4.7 million cycles and other service load and cracking tests did not impact overall system behavior





See also results on previous slide



# Full-Scale Beam Testing – Two Beam Systems

- Observations

3. Transverse tension in precast beams and across joints remained below estimate cracking strains on top and bottom of systems for all service tests






Tension strains shown from these cracking load protocols were highest observed on top of specimens and across joints



# Full-Scale Beam Testing – Two Beam Systems

- Observations



4. Joint demand (measured using transverse CSGs, CDTs across joint, and RSGs on joint reinforcement) decreased when a moment restraint was provided on one end of FIU-4/5



# Full-Scale Beam Testing – Two Beam Systems



- Observations

5. Small compression strains ( $< 50 \mu\epsilon$ ) were measured in service and fatigue load configurations. Larger tensile strains ( $> 300 \mu\epsilon$ ) were measured during strength testing (LC 2-1) but remained less than yield strains.



# Full-Scale Beam Testing – Two Beam Systems

- Observations
  6. No signs of bond deterioration between joint reinforcement and UHPC in joint in any fatigue service, or strength testing



# Implementation

- Observations from Construction

## Side Forms and Joint Construction of Large-Scale Specimens



Paint side forms with paste retarder



Remove side forms 24h after casting



Pressure wash concrete cover




Finalized exposure

### Joint Reinforcement Length <sup>casting</sup>



Variable joint reinf. lengths



Variable joint reinf. lengths cuts

### Retarder Finishes\*



Light penetration (1/8 inch.)



Medium light penetration (1/4 inch.)

\*Based on Master Finish HV Retarder Lilac (Light) and Pink (medium light)

# Implementation

- Observations from Joint Casting

## Joint Surface Preparation



Saturated Surface Dry (SSD) condition

## Formwork Preparation and UHPC Pour



Joint Formwork preparation



UHPC Joint cast from one end



Rodding of two UHPC pour heads



Joint Formwork removal after 24h



## Joint Grinding Action

Grinding action of UHPC overpour



Final joint finish



# Implementation


- Span Ranges and Approximate Number of Strands\*

Span (ft)	FSB	
	48 in.	60 in.
20	12 (8)	12 (9)
30	12 (12)	12 (15)
40	15 (15)	15 (18)
50	18 (16)	18 (21)
55	18 (-)	18 (25)

60	21 (22)*	21 (26)*
70	24 (27)*	24 (33)*
80	30 (33)*	27 (43)*

\*Non-standard thicknesses  
Legend: Thickness (#strands)

\*Using FDOT Design MathCAD Program



Reference: [Chitty, F., Freeman, C., and Garber, D. \(2020\) "Joint Design Optimization for Accelerated Construction of Slab Beam Bridges"](#)

# Thank You



DEPARTMENT OF CIVIL AND  
ENVIRONMENTAL ENGINEERING

Francisco Chitty, PhD

[fchitty@finfrock.com](mailto:fchitty@finfrock.com)

Design Engineer  
FINFROCK

David Garber, PhD, PE

[dgarber@fiu.edu](mailto:dgarber@fiu.edu)

Associate Professor  
Florida International University

Christina Freeman, PE

[Christina.Freeman@dot.state.fl.us](mailto:Christina.Freeman@dot.state.fl.us)

Professional Research Engineer  
Florida Department of  
Transportation



THE WORLD'S GATHERING PLACE FOR ADVANCING CONCRETE

aci CONCRETE  
CONVENTION